

Prefabrication for Architects

Considerations in Designing Mass Timber Buildings



Canadian
Wood
Council

Conseil
canadien
du bois



Module 1: Introduction and Project Planning for Optimizing Design

Objectives:

Introduce the prefabrication process of mass timber and early design considerations to optimize design.

- Introduction to mass timber
- Advantages to Prefabrication
- Early considerations for optimizing design
- Project planning



An aerial photograph of a vast, dense forest. The majority of the trees are dark green, suggesting evergreens. Scattered throughout the canopy are patches of trees with yellow and orange foliage, indicating the onset of autumn. The lighting is soft, creating a rich, textured appearance of the forest floor and canopy.

Regenerative



Mass Timber

- Engineered products made from dimensional lumber
- Laminated together through the elimination process
- Forms large structural elements
- Lamination occurs through adhesive, nails, screws, or dowels

Cross Laminated Timber

Glulam

Dowel Laminated Timber

Nail Laminated Timber

Mass Plywood




Canadian
Wood
Council

Conseil
canadien
du bois




Image of a CLT Panel in the fabrication process. Photo by: Veronica Madonna

Mass Timber Products




Cross Laminated Timber



Glued Laminated Timber



Nail Laminated Timber



Dowel Laminated Timber



Mass Plywood Panel



Laminated Veneer Lumber



Glulam and Glulam Panels (GLT)



**Dimensional Lumber stacked
parallel to each other
Long spans and strength**



Image of a glulam beam structure and decking. Source: StructureCraft

Cross Laminated Timber (CLT)



**Dimensional lumber stacked
crosswise
Strength, dimensional stability and
rigidity**



The Cube in Hamburg, Germany, is constructed using CLT panels for floor and wall structure. Photo credit IBA Hamburg, Martin Kunze.



Nail Laminated Timber (NLT)



NLT consists of dimensional lumber placed on edge with individual pieces mechanically fastened together by nails or screws



The interior of 80 Atlantic Avenue in Toronto, Ontario architectural designed by BPN Quadrangle (formerly Quadrangle Architects Ltd.) utilizes a nail-laminated timber floor deck. Photo credit: Doublespace Photography.

Dowel Laminated Timber (DLT)



Like NLT, except it is fastened together using wood dowels rather than metal screws or nails



Image of the DLT floor structure at 111 East Grand Office. Source: StructureCraft

Mass Plywood Panels (MPP)



**Veneer-based engineered panel
comprised of multiple veneers
pressed and adhered together**



Image of a mass plywood pavilion. Source: Lever Architecture.

Advantages of Mass Timber



Construction Advantage

Prefabrication on components provide greater precision and quality control.

Reduced on-site construction.

Speed and cost
Human connection
sustainability



Aesthetic Advantage

Aesthetic and experiential benefits often make mass timber buildings desirable to tenants as well as aiding in biophilic benefits.



Ecological Advantage

Building represent close to 40% of the greenhouse gas emissions.

Wood has the ability to sequester carbon, and is a low embodied carbon building product.



Additional Advantages


Proven Performance and Safe

Light-weight and Low Embodied
Carbon Material


Efficient, Cost-Saving Construction

Thermal and Health Benefits

Social, Economic, Environmental and Cultural Benefits




Life Cycle Overview of Mass Timber



Carbon Emissions

Global CO₂ Emissions by Sector




Source: © 2018 2030, Inc. / Architecture 2030. All Rights Reserved. Data Sources: UN Environment Global Status Report 2017; EIA International Energy Outlook 2017

- Buildings contribute to over 40% of the total green house emissions globally
- Annually, embodied carbon is responsible 11% of global GHG emissions and 28% of global building sector emissions.

Source: Architecture 2030

Embodied vs. Operation Carbon

Total Carbon Emissions of Global New Construction
from 2020-2050
Business as Usual Projection



© 2018 2030, Inc. / Architecture 2030. All Rights Reserved. Data Sources: UN Environment Global Status Report 2017; EIA International Energy Outlook 2017

- Embodied carbon will be responsible for *almost half* of total new construction emissions between now and 2050.
 - Unlike operational carbon emissions, which can be reduced over time with building energy efficiency renovations and the use of renewable energy, embodied carbon emissions are locked in place as soon as a building is built. It is critical that we get a handle on embodied carbon now if we hope to phase out fossil fuel emissions by the year 2050.



Activity – Understanding Mass Timber



1. *Name three mass timber products and how they compare.*
2. *What are three advantages of mass timber?*
3. *Describe the four benefits to utilizing mass timber.*



Advantages of Prefabrication



Mass Timber and Prefabrication



<https://www.canadianarchitect.com/home-products-r-hauz-toronto-ontario-and-intelligent-city-vancouver-british-columbia/>

Modular construction's time may have finally come

The benefits

Modular construction can speed construction by as much as

50%

In the right environment and trade-offs, it can cut costs by

20%

The opportunity

Modular construction could claim

\$130B


of the market by 2030 in U.S./Europe at moderate penetration, delivering annual cost savings of

\$22B

This would help fill a

\$1.6T

productivity gap identified in 2017



Driving demand

Labor and housing shortages are the biggest predictors of where modular construction can gain traction



e.g. Australia, UK, Singapore, U.S. West Coast

All industry participants will need to make big changes



Modular manufacturers: Scale and optimize



Developers: Productize and partner



Materials suppliers: Prepare for a shift in products and go-to-market; or enter the space



Public sector: Bundle pipelines and update building codes



Engineering & construction firms: Preempt commoditization



Investors: Seek to understand new opportunities

Benefits of Modular Construction

20-50% increase speed of construction

Potential cost savings of 20%

Big changes are required

- Modular manufacturers
- Developers
- Suppliers
- Regulations
- Design & Engineering
- Investments

Source: McKinsey & Company . (2019, June). *Modular Construction: From Projects to Products*. Retrieved from McKinsey & Company




Canadian
Wood
Council

Conseil
canadien
du bois



Construction Advantage



Brock Commons Tall Wood House during construction. Architect: Acton Ostry, Structural Engineer: Fast+Epp. Photo by: KKLaw

Construction speed

- Potential 25% quicker than traditional material like concrete
- 90% reduction in truck deliveries
- 75% fewer works on active deck

Light Weight Structure

- Can reduce foundation sizes

Prefabrication = Less Waste

- Precision in fabrication process
- Greater quality and quality control

Modular Construction




Canadian
Wood
Council

Conseil
canadien
du bois



Modular construction covers a broad set of approaches.

Complexity and scale of modular construction—comparison of approaches




Various Approaches to Prefabrication

Source: McKinsey & Company . (2019, June). *Modular Construction: From Projects to Products*. Retrieved from McKinsey & Company

Prefabrication and Potential Scenarios

A project's specific requirements will determine the choice of modular system.



3D Volumetric Prefabrication



- Fully Assembled Units
- Maximize productivity benefits and efficiencies
- However, limitation include transportation
 - Typically, 3.5m wide for non-police escort
- Compartmentalized plans
 - Hotels
 - Student Residence
 - Affordable Housing

Source: 3D Volumetric Construction of Hotel Jakarta in Amsterdam.
<https://www.derix.de/en/referenzen/X-LAM/hoteljakarta>



2D Panelized



- Panels prefabricated off-site and assembled on site
- Flat packed for shipping, more economic shipping costs than 3D Volumetric
- However, longer times on site than 3D Volumetric
- Permits flexibility for open plan design, ie. Offices

Albina Yard in Portland Oregon by LEVER Architecture. Photo by: Jeremy Bittermann



Early Considerations For Optimizing Design



Project Planning

Project Planning and Time Distribution






Figure 9: Compressing the Typical Construction Schedule with Mass Timber. Potential cost savings in comparison to steel and concrete. (WoodWorks 2019)


Traditional Project Delivery - Design-bid- build




Cooperative Planning



Integrated Design And Project Delivery





The Integrated Team



Key Planning Considerations



Integrated design process to ensure careful considerations of building use, site considerations, structure, systems integration and construction sequencing.



Sufficient time must be budgeted in the planning stages.



Enhanced coordination of systems during the design process.



Prefabrication and detail planning are critical to resolve before construction.



Significantly reduce time during the construction stage and heightened overall quality control.



Manufacturer Input



- Capabilities for product and sizes
- Optimize size
- Reduce waste

Albina Yard in Portland Oregon by LEVER Architecture. Photo by LEVER Architecture.




Kit of Parts



Brock Commons Tall Wood House. Architects: Acton Ostry Architects, Structural Engineer: Fast + Epp, Photo By: Pollux Chung



Know Your Product and Supply Chain March 2021



EUROPEAN SUPPLIERS

- Storaenso
- KLH
- Binderholz
- Hasslacher
- Mayr Melnhof



Canadian
Wood
Council

Conseil
canadien
du bois





Activity – Integrated Design Process

1. *Describe the differences between the design-bid-build and the integrated design process (IDP). Provide a diagram of the relationships. Consider:*
 - a. *What are the key advantages to IDP in mass timber buildings?*
 - b. *What is the collaboration process critical?*



Module 2: Design Considerations for Optimized Design

Objectives:

Understand key design considerations to optimize design for prefabrication of mass timber design.

- Structural design considerations
- Fire protection design considerations
- Acoustic and vibration design considerations
- Retrofits and adding storeys to existing building design considerations

Design Consideration of Mass Timber Design



Mactan Cebu
International Airport Terminal 2,
Cebu City, Philippines.



Structural Design Considerations

Selecting a Mass Timber System

- Strength and stability
- Load capacity
- Program and use
- Long term flexibility

Installation of glulam beam during the construction of the First Tech Credit Union headquarters building in Hillsboro, Oregon.

Source: <https://www.capitalpress.com>



Canadian
Wood
Council

Conseil
canadien
du bois



Common Timber Systems

Framed Systems

Panelized Systems

Hybrid Systems



Structural System and Program Use

Structural System and Program Use



Key Considerations



Program Use



Cost



Fire Protection



Vibration and
Acoustic Control



Authorities and
Code Requirements



Factors in Selecting a Structural System

Cost

- Cost of design
- Cost of materials
- Cost of transportation
- Cost of installation
- Cost of protection and maintenance

Schedule

- Shop drawings and approvals
- Materials acquisition
- Construction productivity

Factors in Selecting a Structural System

Function

- Clear span
- Program requirements and long-term flexibility
- Depth of members and clear height
- Location of bearing walls and other supports
- Incorporation of mechanical and electrical systems
- Thermal insulation

Code Requirements

- Fire protection
- Sound transmission
- Structural capacity
- Durability

Factors in Selecting a Structural System

Aesthetics

- Appearance of material
- Appearance of finished system
- Architectural blend of form and function

Environmental

- Environmental impact of harvesting, mining, quarrying, and manufacture
- Energy required to manufacture, transport, and install materials
- Thermal efficiency of building systems
- Disposal, recycle or reuse at end-of-life cycle

Framed Structural System

Framed System - 9x9m GRID

Economical

Deep structure
5-stories, perhaps 6-stories depending
on floor-to-floor height requirements

Girders and Purlins

Target Occupancy Type: Office
Grid Spacing: 9m x 9m

Column Size: 456 x 390 mm
Girder Size: 265 x 874 mm
Purlin Size: 215 x 570 mm

Deck:


Fire Rating = 60 minute min.
TYP. 3-ply CLT Encapsulated
TYP. 5-ply CLT Exposed

Total Structural Depth: 1013mm

Alternative Deck:
NLT / DLT / GLT

Mechanical Considerations

Underfloor air distribution
Radiant ceiling panels or chilled
beams



Ontario Secondary School Teachers' Federation



Moriyama & Teshima Architects, www.mtarch.com



Canadian
Wood
Council

Conseil
canadien
du bois



Framed System - 6x9m Grid

Economical

Open span between girders for overhead system distribution (no purlins)
Deep structure

Long Beam, Short Deck

Target Occupancy Type: Office
Grid Spacing: 9m x 6m

Column Size: 418 x 365 mm
Girder Size: 265 1178 mm

Deck:
Fire Rating = 60minute min.
235mm NLT / DLT with 5/8" plywood



Total Structural Depth: 1413 mm

Alternative Deck:
9-ply CLT or GLT

Total Structural Depth:
1531 mm

Mechanical Considerations

Overhead system distribution,
distribution between girders



80 Atlantic Avenue – Toronto Ontario



Quadrangle Architects
<https://www.archpaper.com/2020/01/80-atlantic-toronto-timber-office-building/>



Canadian
Wood
Council

Conseil
canadien
du bois



Framed System - 3x4m Grid

Economical

Shallow structure
Short bay

Short Span

Target Occupancy Type: Residential
Grid Spacing: 9 m x 9 m

Column Size: 266 x 265mm
Girder: 265 x 228 mm

Deck:
Fire Rating = 60 minute min.
5-plyCLT partially exposed

Total Structural Depth: 367 mm

Alternative Deck:
89 mm NLT / DLT or GLT

Total Structural Depth:
317 mm

Mechanical Considerations

Unit mechanical
Overhead distribution
Partial dropped ceiling or reduced head


Point Loaded CLT

Short Span
Occupancy Type: Residential

Grid Spacing: 4 m x 2.45 m

Deck:
Fire Rating = 60 minute min.
5-plyCLT partially exposed *

* Encapsulation may be required
dependent on fire loads



Brock Commons Tall Wood House



Acton Ostry Architects



Canadian
Wood
Council

Conseil
canadien
du bois



Timber Bay Design Tool – Fast + Epp Concept Lab

<https://www.fastepp.com/concept-lab/timber-bay-design-tool/>

Timber Bay Design Tool


Explore multiple options for mass timber grids by adjusting the parameters below. Approximate calculations will be performed in the background to size up the deck, purlins, girders, and columns and display them all in 3D. See the bay data output table for these results along with structural depth and material takeoffs. Reduce the timber volume and you will reduce the cost. An imperial version and PDF tool is coming soon!

Keep in mind, these member sizes are approximate and are to be used for preliminary design exploration only. By using this application, you are agreeing to our [Terms and Conditions](#).

FAST + EPP

Grid Dimension: 9m Grid Dimension: 9m Number of Purlins: 3 Building Stories: 6 Panel Type: CLT Loading: Residential Fire Resistance: 0 min Purlin Width: 215mm Girder Width: 265mm

☒ Show dimensions



Bay Data

Panel Size:
87V CLT (3PLY)

Girder Size:
265w x 608h

Purlin Size:
215w x 456h

Column Size:
342w x 315h

Total Structural Depth:
695mm

Column Spacing:
9000mm x 9000mm

Material Volume

Glulam Volume:
0.075m³/m²

Panel Volume:
0.087m³/m²

Total Timber Volume:
0.162m³/m²



Canadian
Wood
Council

Conseil
canadien
du bois



Member Calculator Tool – Fast + Epp Concept Lab

<https://www.fastepp.com/concept-lab/calculator/>

Calculator

Follow the step by step process below to find approximate member depths of various structural components.

Keep in mind, these member sizes are approximate and are to be used for preliminary design only.



By using this application, you are agreeing to our [Terms and Conditions](#)

FAST + EPP

1 Select Material:



2 Select Structure:



Canadian
Wood
Council

Conseil
canadien
du bois





Activity – Factors in Selecting a Structural System

1. *Name the six factors described in selecting a structural system.*
2. *Utilizing the Fast + Epp Concept Lab Timber Bay sizing tool, calculated the size of the structural members of the following structural grid spans.*
 - a) *8x6m Office Building, 6 stories with a 60 min fire resistance rating.*

Describe the advantages and challenges in design choices available for the scenario.



Hybrid System

Hybrid System - Concrete and Wood Composite Slab

9x7m Grid

Shallow Structure

Flat slab, shallow structure
Cost Premium
6 stories possible

Flat Slab

Target Occupancy Type: Office

Grid Spacing: 7m x 9m


Column Size: 400 x 1200 mm
Flat Slab Beam: 9-ply CLT

Composite slab:
5-ply CLT
50mm concrete

Total Structural Depth: 365 mm

Mechanical Considerations

Underfloor air distribution or
overhead system distribution



The Arbour at George Brown College



Moriyama & Teshima Architects and Acton Ostry Architects



Canadian
Wood
Council

Conseil
canadien
du bois



Hybrid System - Steel Delta Beam with Wood and Concrete Composite Slab

Shallow Structure

Flat slab to minimize floor-to-floor heights
Cost Premium,
Delta Beam Propriety

Flat Slab

Target Occupancy Type: Office
Grid Spacing: 8m x 8m

Column Size: 400 x 1200 mm
Flat Slab Beam: 9-ply CLT

Composite slab:
150mm concrete on 175mm CLT


Alternative:
315mm CLT

Alternative Deck:
9-ply CLT

Total Structural Depth:
1531 mm

Mechanical Considerations

Underfloor air distribution or
overhead system distribution



77 Wade Avenue, Toronto Ontario



BNKC Architects



Canadian
Wood
Council

Conseil
canadien
du bois



80 M Street, Washington D.C.



Figure 44: 80 M Street in Washington D.C. is a vertical expansion of an existing building. Source: Think Wood.

Panelized System

Cross Laminated Timber Panelized System

Vertical and horizontal loads

Cross Laminated Timber Panels
Load Bearing
Modular, potential cost savings
Compartmentalized planning

Cross Laminated Timber

Target Occupancy Type: Residential
Grid Spacing: 6m x 12m



Panel Width – 3.0m / 2.4m / 1.6m
Max Panel Length – 12m – 19.5*
Max panel Thickness: 89mm – 267 mm

Panel Tolerance –
+/- 3mm width
+/- 6mm panel length*

* CLT panel dimensions vary between

Mechanical Considerations

Coordination through panels



The Cube – Hamburg, Germany



The Cube in Hamburg, Germany, is constructed using CLT panels for floor and wall structure.

Photo credit IBA Hamburg, Martin Kunze.

Case Study: R-Hauz R-Town, Toronto Ontario

Panelized Cross-Laminated Timber (CLT)



Concept rendering of the front elevation along Queen Street East in Toronto, Ontario. Image Source: www.r-hauz.ca.

Case Study R-Hauz, R-Town

Developer: R-Hauz

Architect: CMV Architects

Structural Engineer: Moses Engineering

Cross-Laminated Timber Panels



Canadian
Wood
Council

Conseil
canadien
du bois



Case Study: R-Hauz, R-Town



Case Study: YWCA Supportive Housing Kitchener-Waterloo, Ontario

Panelized Cross-Laminated Timber (CLT)

Case Study: YWCA Supportive Housing



Concept rendering of the proposed exterior of the YWCA Supportive Housing. Image Source: Edge Architects and Element5.

Architect: Edge Architects

Owners: YWKW

Developer: Melloul Blamey Construction

Mass Timber Fabricator: Element5

Cross-Laminated Timber Panels



Canadian
Wood
Council

Conseil
canadien
du bois



Case Study: YWCA Supportive Housing



Concept rendering of the interior of the ground floor amenity space. The structural grid in this location shifts from a panelized system to a post and panel system. Image Source: Edge Architects and Element5.





Diagram of cross-laminated timber panel distribution.
Image source: Edge Architects and Element5.


Case Study: YWCA Supportive Housing



Structural cross-laminated timber floor panels

Structural cross-laminated timber wall panels

Structural glulam column




Left: Diagram of Element5's CLIP system. Right: Building Diagram illustrating the prefabricated mass timber structural system and exterior envelop components. Image Source: Edge Architects and Element5.

Case Study: YWCA Supportive Housing

01

Planning and Approvals


Architectural plans are adapted to the chosen site and submitted for any municipal approvals and permits. Element5 develops shop drawings and begins manufacturing the structural components in their factory.



02

Site Work Begins


Once plans are approved, site work and grading can commence. Meanwhile, production continues on the structural components off-site at the Element5 factory.



03

Foundation


Foundations are poured on-site.



04

Super Structure


Modular wall, floor, and roof panels arrive on-site. They are then craned into place to create the super structure.



05

Envelope Panels

Modular, prefabricated exterior wall panels arrive on-site. They are then craned into place to quickly enclose the building.



06

Completion

Once the envelope has been installed, the interior can be completed. Final landscaping and other site work is completed simultaneously.




Diagram and description of the process and sequencing of construction.
Image Source: Edge Architects and Element5.



Designing for Fire Protection

Fire Protection – Key Considerations



Low-rise, Mid-rise, High-rise Code Requirements



Passive Fire Protection Strategies



Active Fire Protection Strategies



Fire Protection During Construction



Passive Fire Protection Strategies

Fire resistant rating of structure in floors

Level of encapsulated material or char consideration

Fire rating of egress routes

Fire separation requirements

Components and systems are intended to contain fire or slow the spread of fires through the use of fire-resistant building elements



Active Fire Protection Strategies


Detection and response systems

- Fire dampers
- Closure of automatic doors
- Fire sprinklers activated
- Fire suppression system activated



FIGURE 2:

Reduction in Member Width and Depth over Time




Source: TR 10, AWC

TABLE 6:**Effective Char Rates and Char Depths**(for $\beta_n = 1.5$ inches/hour)


Required Fire Endurance (hours)	Char Depth, a_{char} (inches)	Effective Char Depth a_{eff} (inches)
1	1.5	1.8
1-1/2	2.1	2.5
2	2.6	3.2

Source: NDS Table 16.2.1A, AWC


Fire Protection – Char Theory



Fire Protection – Encapsulation



Detail of typical column and floor intersection and encapsulation, by Fast + Epp.



Source: Denis Blount, ARUP – “Knock on Wood: Acoustical Design in Mass Timber Structures”.

Fire Protection Case Study – Brock Commons Tall House

Fire Safety During Construction



High-Rise

- Less than four levels of unprotected wood during construction.
- Protection of wood structural elements by installing a layer of Type X gypsum board and concrete topping as structure is built.
- Functional standpipe in concrete cores.
- On-site security and fire watch

Image: Source: Think Wood, <https://www.thinkwood.com/projects/brock-commons-tallwood-house>

Image: Source: Think Wood, <https://www.thinkwood.com/projects/brock-commons-tallwood-house>



Canadian
Wood
Council

Conseil
canadien
du bois



Carbon 12 – Portland Oregon

Fully Exposed Mass Timber

Maximum height: 9 stories; 85 feet

Maximum area: 405,000 SF total building; 45,000 SF average per floor

Fire-rating requirements: 2-hour primary frame; 2-hour floors




Image Source:
<https://www.kaiserpath.com/carbon12>
Images: Andrew Pogue, Marcus Kauffman



Designing for Acoustics and Vibration




Acoustics – STC vs IIC



Sound Transmission Class (STC) – Airborne

- “Through” partitions
- Around partitions (flanking)
- Through structural coupling



Impact Sound Isolation (IIC) – Impact

- Through floor assemblies
- Through structural coupling

Improving Acoustics




Add Mass

Mass provides weight to mitigate transfer of low frequency sounds.
For example, impact noise.



Add Noise Barriers

Add insulation and other acoustic absorptive material




Add Decouplers

Resilient layers to “separate” materials provides decoupling to reduce the transfer of vibration.




Acoustics – Flanking Control


- Decoupling of floor topping at CLT
- Decoupling walls from space below
- Acoustic sealant at partition joints





Source: Denis Blount, ARUP – “Knock on Wood: Acoustical Design in Mass Timber Structures”.

Acoustic Treatments on CLT Floor Assembly

Sketch and Short Description	STC Rating	IIC Rating
 <p>Bare CLT 5 ply (175 mm)</p>	42	26

Sketch and Short Description	STC Rating	IIC Rating
 <p>CLT 5 ply (175 mm) with one layer of 16 mm Type X gypsum board installed on Z channels</p>	62	48


Sketch and Short Description	STC Rating	IIC Rating
 <p>38 mm (1-1/2") precast concrete slab on 13 mm (1/2") rubber membrane placed on top of a CLT 5 ply (175 mm).</p>	56	48

Sketch and Short Description	STC Rating	IIC Rating
 <p>38 mm (1-1/2") precast concrete slab on 9 mm closed cell foam placed on top of a CLT 5 ply (175 mm) with one layer of 16 mm Type X gypsum board installed on Z channels.</p>	70	56


Reference: Canadian CLT Handbook – 19th Edition, FP Innovations

Source: Denis Blount, ARUP – “Knock on Wood: Acoustical Design in Mass Timber Structures”.


Acoustic Treatments on CLT Wall Assembly




	Wall Composition	Airborne (STC) dB
1	3-layer CLT panel (95 mm ~ 115 mm)	≤ 32~34



	Wall Composition	Airborne (STC) dB
1	Gypsum board 15 mm	≤ 36~38
2	3-layer CLT panel (95 mm ~ 115 mm)	
3	Gypsum board 15 mm	



	Wall Composition	Airborne (STC) dB
1	Gypsum board 15 mm	≤ 58
2	Mineral wool (~ 60 mm)	
3	Lumber studs (38 mm x 63 mm)	
4	3-layer CLT panel (95 mm ~ 115 mm)	
5	Mineral wool (~ 60 mm)	
6	Lumber studs (38 mm x 63 mm)	
7	Gypsum board 15 mm	



	Wall Composition	Airborne (STC) dB
1	Gypsum board 15 mm	≤ 60
2	3-layer CLT panel (95 mm ~ 115 mm)	
3	Sound insulation material (rock wool) (~ 30 mm)	
4	Sound insulation material (rock wool) (~ 30 mm)	
5	3-layer CLT panel (95 mm ~ 115 mm)	
6	Gypsum board 15 mm	

Reference: Canadian CLT Handbook – 19th Edition, FP Innovations

Source: Denis Blount, ARUP – “Knock on Wood: Acoustical Design in Mass Timber Structures”.

Other Design Considerations

- Full scale mockups
- Fire proofing of connectors
- Vibration and Acoustics
- Approval Process and AHJ
- Insurance Requirements
- Temporary fire protection during construction
- Onsite Security and Protection
- Supply Chain

CLT floor slab is lowered into place and fastened to the glulam columns. Photo: KK Law, Courtesy of Naturally: Wood.



Activity – Understanding Fire Protection and Acoustics



1. *Name the various passive and active strategies involved in designing for fire protection of mass timber buildings.*
2. *What are the two main acoustic concerns when it comes to mass timber buildings?*
3. *What are the three main ways to improve acoustical performance and what are some of the key considerations of each?*



Retrofits and Adding Storeys to Existing Buildings

Adding Stories to Existing Buildings and Mass Timber



Illustration representing design opportunities with adding storeys to an existing building. Concept rendering by Studio Veronica Madonna Architect.

Consideration of Mass Timber and Adding Stories



South Boston Rivet Factory



Adding storeys to South Boston Rivet Factory, by Margulies Perruzzi Architects.




Canadian
Wood
Council

Conseil
canadien
du bois







South Boston Rivet Factory



Source: <https://www.enr.com/articles/51022-former-south-boston-rivet-factory-gets-heavy-timber-upgrade>

Resources



Canadian
Wood
Council

Conseil
canadien
du bois



Module 3: Early Construction Consideration

Objectives:

Understand the key early construction consideration involved with prefabrication and mass timber design.

- Building Information Modelling (BIM) and Design for Manufacturing and Assembly (DfMA)
- System Integration
- Envelop and Moisture Considerations
- XXXX

Assignment: Embodied Carbon Comparison



Automation and Industrialization of Mass Timber



Image of an automated fabrication process of mass timber, Kateria.

Source: www.kateria.com.



wood
SMART

Canadian
Wood
Council

Conseil
canadien
du bois



Benefits of Prefabrication



Less noise, dust and
site disruption



Improved health
and safety



Continuity of
employment



Workforce
upskilling



Predictable product
performance




Lower product
operational costs






Image of Element5's new factory in Ontario. Source: Element5








Importance of BIM and DfMA Integration




Integration of BIM amongst the owner, design and construction team.

Virtual Design and Construction Modelling




Brock Commons Tallwood House utilized various levels of Virtual Design and Construction Modelling throughout the design and construction process. Source: Wood-Works, Brock Commons Tallwood House: Construction Modelling.

Mass Timber Factory



Layout of the new CLT line for Element5's new state-of-the-art mass timber facility in St. Thomas, Ontario. Source: www.ledinek.com

Digital Twin / Virtual Design and Construction Model



Video – Digital Twin, Virtual Design and Construction Modeling

<https://www.youtube.com/watch?v=ATKpFtzCVFU>





Next Generation

Mass Timber research at ETH Zurich.
Robot – dimROB

Source: “Mobile Robotic Fabrication on
Construction Sites: DimRob”





Activity – Benefits of Prefabrication

1. Which of the following is a benefit of wood prefabrication?

- a. Process efficiency
- b. Controlled environment
- c. Material efficiency
- d. Sustainability
- e. All of the above

2. *Name all six identified benefits of prefabrication.*



System Integration

Prefabrication and System Integration



Right: Image by Cadmakers illustrating the level of detail involved in coordinating MEPF systems for fabrication. Left: Image of plumbing shelving and penetrations through CLT slab (Photo source Structurlam).



Wood Innovation Centre, University of Northern British Columbia
Source: Michael Green Architecture



Canadian
Wood
Council

Conseil
canadien
du bois





80 Atlantic Avenue, Toronto
Source: Quadrangle Architects



Canadian
Wood
Council

Conseil
canadien
du bois



Case Study: Brock Commons Tallwood House

University of British Columbia



Canadian
Wood
Council

Conseil
canadien
du bois





dential

Brock Commons Tallwood House

18 storeys
53 metres high

PROJECT CREDITS

OWNER

University of British Columbia,
Student Housing and Hospitality Services

OWNER'S REPRESENTATIVE

University of British Columbia,
Infrastructure Development

PROJECT MANAGER

UBC Properties Trust

ARCHITECT OF RECORD

Acton Ostry Architects Inc.

TALL WOOD ADVISOR

Architekten Hermann Kaufmann ZT GmbH

STRUCTURAL ENGINEER

Fast + Epp

MECHANICAL, ELECTRICAL, FIRE PROTECTION ENGINEER / LEED CONSULTANT

Stantec

BUILDING CODE & FIRE ENGINEERING

GHL Consultants Ltd.

BUILDING ENVELOPE & BUILDING SCIENCES

RDH Building Science Inc.

ACOUSTICAL ENGINEER

RWDI AIR Inc.

CIVIL ENGINEER

Kamps Engineering Ltd.

LANDSCAPE ARCHITECT

Hapa Collaborative

BUILDING ENERGY MODELLING

EnerSys Analytics Inc.

VIRTUAL DESIGN & CONSTRUCTION MODELLERS

CadMakers Inc.

CONSTRUCTION MANAGER

Urban One Builders

DESIGN-ASSIST TRADES

Structurlam Products LP

Seagate Structures

Whitewater Concrete Ltd.

COMMISSIONING CONSULTANT

Zenith Commissioning Consulting

Brock Commons Overview – Video 1


<https://www.youtube.com/watch?v=G22kYhaT-h4>



Brock Commons



Virtual Design and Construction Modelling



Render of hybrid mass timber and concrete structure, by CadMakers Inc.





Brock Commons



Canadian
Wood
Council

Conseil
canadien
du bois



*BROCK COMMONS
TALLWOOD HOUSE:
CONSTRUCTION
OVERVIEW*




Brock Commons Design Process – Video 2

https://www.youtube.com/watch?v=ABQHbNwvU_s



Brock Commons Project Schedule Overview



A overview of the project schedule.

Laura Gilmore

Full-Scale Mock-Up



Brock Commons

Construction Planning



Photography by KK Law

Kit of Parts



Brock Commons



Canadian
Wood
Council

Conseil
canadien
du bois



Brock Commons Construction Process – Video 3

<https://www.youtube.com/watch?v=Fmuj4XeHsbo>





Activity – Benefits of VDC Modelling


Describe the benefits of VDC modelling. What advantages did it offer on the Brock Common's Tallwood House and why was it an important aspect of the success of the project?



Envelop & Moisture



Envelop and Enclosure




The Arbour, Moriyama & Teshima Architects / Acton Ostry Architects

Temporary Protective Roofing




Temporary protective roofing at the Limnologen Vaxjö construction site, Sweden.



Prefabricated Envelopes

Source: Island Exterior



Managing the Risk of Water Damage During Construction



<https://www.surfacesreporter.com/articles/72301/mass-timber-architecture-benefits-and-common-misconceptions>



Canadian
Wood
Council

Conseil
canadien
du bois





Managing the Risk of Fire During Construction

- Fire protection system
- Clean site, reduce flammable
- Hot work, such as welding, was done ahead of the mass timber structure installation.
- All trades were required to take fire-prevention and fire response training.
- Temporary fire doors were installed on the two exit stairs and clear exit paths were maintained.

Module 4: Life Cycle Assessment

Objectives:

Describe Life Cycle Assessment and the consideration involved in holistic design.

- Holistic considerations of carbon
- Why is LCA and Carbon Analysis Important
- Life Cycle Assessment Tools
- Biophilia, Health and Wellness



Holistic Considerations of Carbon

Looking Towards The Future

Life Cycle Assessment

Life Cycle Assessment (LCA) is a cradle-to-grave analysis technique to assess environmental impacts associated with all the stages of a product's life.

The five key stages of LCA include:

Manufacturing


Packaging

Distribution

Use

Disposal

Raw Materials



The Process of Whole-Building LCA




Figure 1: Life cycle phases of a building

Source: Athena Sustainable Materials Institute, "About Whole-Building LCA and Embodied Carbon," 2019.

Operational Carbon

OPERATIONAL CARBON is defined as the greenhouse gas emissions associated with the operational energy use of a building. This includes all carbon from energy required to heat and power the building, including but not limited to lighting, plug loads, heating and cooling, and cooking.

A dramatic, low-angle shot of a steel mill interior. A large, glowing orange molten metal ladle is being poured into a mold, creating a massive spray of sparks and steam. The scene is filled with industrial structures, including scaffolding and pipes, all bathed in the intense orange light of the molten metal.

Embodied Carbon

EMBODIED CARBON is defined as the greenhouse gas emissions associated with the raw material extraction, manufacturing and processing, transportation, and installation of all building materials.

Net-Zero Carbon

NET-ZERO CARBON is defined as the combined operational and embodied carbon being resolved as zero through material selection, renewable energy and approved appropriate offsets.

LCA / LCI / LCIA and LCC

Life Cycle Assessment (LCA)

- Calculating the lifetime environmental impact of a product or service.

Life Cycle Inventory (LCI)

- Data collection portion of LCA. The accounting of everything involved in the system.

Life Cycle Impact Assessment (LCIA)

- What does it mean? The inventory is analyzed for environmental impact.

Life Cycle Costing

- Direct monetary cost involved with a product or service on the environmental.

Life Cycle Assessment



What is being taken from our Resources, Water and Energy?



Cradle-to-Gate
Raw Material Acquisition,
Manufacturing, Products
and Assemblies



On-Site Construction
Building Construction,
Use/Waste



**Operations and
Maintenance**
Use, Reuse and
Maintenance



End-of-Life
Products/Materials.
Recycle/Reuse, and
Waste Management

What is being emitted back into the Air, Water and Land?



Whole-Building LCA Explained

LCA looks at cradle-to-grave lifetime of buildings including as resources are consumed and emissions created during each phase of a building's life span.

- Manufacturing and transportation of construction materials
- Process of construction
- Long phase of building occupancy and maintenance
- Demolition
- Removal of waste materials



Activity - Life Cycle Assessment

What is the definition of Life Cycle Assessment and what are the five stages of consideration?

What are five phases of a building?



Why is LCA and Carbon Analysis Important?

Working Towards Climate Stability




2060 Global Building Stock

Over the next 35 years,

2.5 trillion ft²

of buildings will be constructed or renovated in cities worldwide



Global Floor Area Growth

© 2018 2030, Inc. / Architecture 2030, All Rights Reserved.
Source: UN Environment Global Status Report 2017
Data Source: IEA (2017), World Energy Statistics and Balances

Architecture 2030, “Why The Building Sector?,” accessed May 12, 2021,
https://architecture2030.org/buildings_problem_why/.




Canadian
Wood
Council

Conseil
canadien
du bois



Global CO₂ Emissions by Sector



Buildings contribute to **over 40% of the total green house** emissions globally


Annually, embodied carbon is responsible **11% of global GHG** emissions and 28% of global building sector emissions.

Source:
2018 Global ABC Report; IEA

Source: Architecture 2030

Why is Reducing Embodied Carbon Important?

Total Carbon Emissions of Global New Construction
from 2020-2050
Business as Usual Projection



© 2020 2030, Inc. / Architecture 2030. All Rights Reserved.
Data Sources: UN Environment Global Status Report 2017; EIA International Energy Outlook 2017




Canadian
Wood
Council

Conseil
canadien
du bois



Embodied vs. Operation Carbon

Total Carbon Emissions of Global New Construction
from 2020-2050
Business as Usual Projection



Embodied carbon will be responsible for
**almost half of total
new construction**
emissions between now and 2050.

© 2018 2030, Inc. / Architecture 2030. All Rights Reserved. Data Sources: UN Environment Global Status Report 2017;
EIA International Energy Outlook 2017

Source: Architecture 2030



Canadian
Wood
Council


Conseil
canadien
du bois



Canada Raising Climate Ambitions

- **Federal Government Announcement - April 21, 2021**
- Go beyond their **30% by 2030**
- Reduce 2005 emission levels by **40-45% by 2030**
- **Net zero by 2050**
- **Price on pollution**
- **Decarbonizing materials**
 - concrete, steel and aluminum
- Will make it law

Accelerating to Zero by 2040




Source: Architecture 2030

50% of wood is carbon



Sustainable Forests Strategy



<https://www.ontario.ca/page/sustainable-growth-ontarios-forest-sector-strategy>



Canadian
Wood
Council

Conseil
canadien
du bois





Activity – Building and Impact on Climate

- Define the following terms:
 - Operational Carbon
 - Embodied Carbon
 - Net-Zero Carbon

Why are each important consideration?

Why is the consideration of embodied carbon critical in achieving climate stability?



Life Cycle Assessment Tools


Gestimat, Athena and Other Tools

Life Cycle Assessment Workflow

- **Data Gaps:** Some important products and processes are missing or incomplete in the Life Cycle Inventory (LCI) databases. Materials and Energy data is fundamental to whole-building LCA.
- **Data Inconsistency and Lack of Detail:** Currently, there could exist variation in the method and quality of the data. Data on materials may be out of date, and may not adequately resemble regional circumstances.
- **Method and Standards Inconsistency:** There may be variation in approach to LCA, which means results may not be comparable across studies.

Gestimat

<https://gestimat.ca>

The image shows the login page for Gestimat, a platform for low-carbon construction. The page has a green background with a large, stylized 'G' logo. The text 'GESTIMAT' is prominently displayed in white, with the tagline 'Toward Low Carbon Construction' below it. There are two input fields for 'Email address' and 'Password'. A 'Sign in' button is located to the right of the password field. Below the login fields, there is a checkbox for 'Administrator' and two links: '→ Create an account' and 'Forgot password?'. At the bottom of the page, there is a navigation bar with links for 'ABOUT', 'CONTACT US', 'HELP', and 'FRANÇAIS'.

Copyright © 2019 GESTIMAT. All Rights Reserved.




Canadian
Wood
Council

Conseil
canadien
du bois



Comparative Analysis - Gestimat

LIGHT-FRAME WOOD SOLUTION



Gestimat – Comparing Results

COMPARING RESULTS



1. Glulam structure
Steel-concrete floors



2. Glulam structure
Steel-CLT floors




3. Glulam structure
CLT floors




4. Concrete structure



GHG emissions by material
(kg CO₂ eq.)



GHG emissions by construction system
(kg CO₂ eq.)



Gestimat – Precalculated Typical Buildings

PRECALCULATED TYPICAL BUILDING



- ✓ Facilitating modeling at predesign phase



Photo: Groupe Robin

Multi-storey Structures

1 to 6 storeys

Grid: 6m x 6m to 9m x 9m

Fondsvert Québec



Photo: Stephane Brugger

Free-span Structures

10, 15 and 20 m

cecobois



Canadian
Wood
Council


Conseil
canadien
du bois



Tool – Athena Impact Estimator



Athena
Sustainable Materials
Institute






Activity - Embodied Carbon Analysis using Gestimat


Using the Gestimat program, perform a carbon comparison analysis of the following building using the following systems:

- Steel
- Hybrid – Steel structure and CLT deck
- Mass timber



Building Specifications:

- Begin with the typical commercial building (start with the predefined building in the system)
- 6 stories
- Total Floor Area: 5400 m²
- Building Footprint: 900 m²
- Location: Toronto, Ontario
- Include Foundations:
 - 15mPA Concrete, 1000m³ Volume
 - 0.5 metric tons of rebar










Veronica Madonna









Modeling status: Trial


Test


Information

<div style="display: flex; justify-content: space-between;"> <div> Project name: <input type="text" value="Test"/> Project number: <input type="text"/> Province: <input type="text" value="Ontario"/> Municipality: <input type="text" value="Toronto"/>  Administrative Region: <input type="text" value="Toronto"/> Expected year of construction: <input type="text"/> Expected budget: <input type="text"/> Description / Notes (optional): <div style="border: 1px solid #ccc; height: 40px; margin-top: 5px;"></div> </div> <div> Type of project: <input type="text" value="New construction"/>  Type of building: <input type="text" value="Offices, City Halls, etc."/>  Number of storeys: <input type="text" value="6"/> Total floor area (m²): <input type="text" value="5400"/> Building Footprint (m²): <input type="text" value="900"/> Analysis version (optional): <input type="text"/> </div> </div>	<div style="text-align: right; margin-top: 10px;"> <input type="button" value="Cancel"/> <input type="button" value="Save"/> </div>
--	---

 Access rights management
 Scenarios Add
 Comparability of the scenarios
 Results
 Scenario selection and reporting



Tools

➤ Building Information Label: Embodied & Operational Carbon



RETScreen[®]
Expert



Athena
Sustainable Materials
Institute



Thornton
Tomasetti
Beacon



Canadian
Wood
Council

Conseil
canadien
du bois

